

**Estimate Abstract**

**OD/363/3478/119899/430091/00075366 : Construction of C C with Paver Block road at Kareshpadu  
Block : Pottangi, Gram Panchayat : Ampavalli  
Created By:APARAJITA PRIYADARSINI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	30.836	Cubic Meter	240.77592	7424.56626912
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	27.612	Cubic Meter	1366.735232	37738.293225984
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.165	Cubic Meter	6279.5318628	126626.76001336
4	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	70.4	Square Meter	217.33913527044	15300.675123039
5	<b>Concrete : AR0307 (Second floor) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	6.3	Cubic Meter	8578.5759556	54045.02852028
6	<b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	150	Square Meter	647.283	97092.45

<b>Total Amount:</b>	338227.77315178
----------------------	-----------------

Provision for Contingency (+) @	5000
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	1772
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	349999.77315178
----------------------	-----------------

<b>Grand Net Total Amount</b>	349999.77315178
-------------------------------	-----------------

**APARAJITA PRIYADARSINI**  
**JE**  
**Pottangi Block**

**ER TOPHAN KUMAR NAYAK**  
**AEE**  
**Pottangi Block**

**RAMKRISHNA NAYAK**  
**BDO**  
**Pottangi Block**