

Estimate Abstract

**OD/354/3367/117640/410600/00064425 : Completion of Incompletion AWC Building at Tulasipalli-2
Block : Bhanjanagar, Gram Panchayat : Dihapadhal
Created By:RABINDRANATH NAIK**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	6.2145	Cubic Meter	240.77592	1496.30195484
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	1.08225	Cubic Meter	572.087432	619.141623282
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	1.5193275	Cubic Meter	5294.83919242	8044.5947931215
4	Other Building Items. : AR1911 (Stainless steel of 304 grade in hand railing using 50mm dia of 2mm) : Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge			
	5.7729118152668	Meter	3129.0244276074	18063.582088393
5	Flooring : AR0816 (Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.			
	6.924	Square Meter	1193.6471348236	8264.8127615186
Total Amount:			36488.433221155	

Provision for PH Work (+) @	15000
Provision for EI Work (+) @	12000
Provision for Contingency (+) @	1000
Display Citizen Board (+) @	1000.56
Any Other Lumpsum (+) @	34511
Provision for survey investigation and quality control (+) @	

Total Amount:	99999.993221155
----------------------	-----------------

Grand Net Total Amount	99999.993221155
-------------------------------	-----------------

RABINDRANATH NAIK
JE
Bhanjanagar Block

NITYANANDA PATRO
AEE
Bhanjanagar Block

BHARATEE DEVI
BDO
Bhanjanagar Block