

Estimate Abstract

**OD/350/3345/117173/398989/00062882 : Const of CC Road from Jemadeipur Goutampur Santosh Patra House to Sani Mandira, W.N-06
Block : Tigiria, Gram Panchayat : Jamadeipur
Created By:Mihir Kumar Sethy**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	1.5857408	Cubic Meter	240.77592	381.80820000154
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	9.768163328	Cubic Meter	1259.372232	12301.753652924
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	12.21020416	Cubic Meter	5655.74829386	69057.841345602
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	7.992133632	Cubic Meter	7145.29790582	57106.175703763
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	10.405136	Square Meter	216.23489289764	2249.9534685454

Total Amount:	141097.53237084
----------------------	-----------------

Provision for Contingency (+) @	1430
---------------------------------	------

Display Citizen Board (+) @	472
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	142999.53237084
----------------------	-----------------

Grand Net Total Amount	142999.53237084
-------------------------------	-----------------

Mihir Kumar Sethy
JE
Tigiria Block

KAILASH DHANDRA SAHOO
AEE
Tigiria Block

Monoswini Das
BDO
Tigiria Block