

Estimate Abstract

OD/370/3554/121217/424970/00062544 : IMPROVEMENT OF ROAD WITH CC ROAD AT PAIKSAHI MAIN ROAD TO SENAPATI HOUSE

Block : Muniguda, Gram Panchayat : Muniguda

Created By:AMBIKA PRASAH DASH

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4.86125	Cubic Meter	240.77592	1170.4719411
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.0002	Cubic Meter	567.017232	3969.2340274464
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	16.91715	Cubic Meter	5265.92279142	89084.405750871
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	14.0004	Cubic Meter	6836.20777954	95709.643396672
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	23.334	Square Meter	216.23489289764	5045.6249908735
Total Amount:			194979.38010696	
Provision for Contingency (+) @				2000

Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	20
Provision for survey investigation and quality control (+) @	

Total Amount:	199999.38010696
----------------------	-----------------

Grand Net Total Amount	199999.38010696
-------------------------------	-----------------

AMBIKA PRASAH DASH
JE
Muniguda Block

VOONA SRINIVASA RAO
AEE
Muniguda Block

KRUSHNA CHANDRA DALAPATI
BDO
Muniguda Block