

Estimate Abstract

**OD/352/3356/117425/402250/00073752 : CONSTRUCTION OF CC ROAD FROM SCHOOL TO TELI SAHI
Block : Parajang, Gram Panchayat : Kualo
Created By:Pinky behera**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0110 (Fine dressing of earth work in ordinary or hard soil in road formation) : Fine dressing of earth work in ordinary or hard soil in road formaton according to the direction of the department including cutting or filling earth upto 0.15m depth of surface.			
	278.709	Square Meter	4.6662	1300.5119358
2	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	7.626846912	Cubic Meter	240.77592	1836.361081936
3	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	19.745870976	Cubic Meter	1418.447232	28008.476029336
4	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	29.7963528	Cubic Meter	6199.17857166	184712.91179138
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	21.2376	Cubic Meter	7629.88263442	162040.39543676
6	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	69.67725	Square Meter	216.23489289764	15066.652691152

Total Amount:	392965.30896636
----------------------	-----------------

Provision for Contingency (+) @	4000
Display Citizen Board (+) @	2000
Any Other Lumpsum (+) @	1034
Provision for survey investigation and quality control (+) @	

Total Amount:	399999.30896636
----------------------	-----------------

Grand Net Total Amount	399999.30896636
-------------------------------	-----------------

Pinky behera
JE
Parajang Block

Rani panda
AEE
Parajang Block

Sauvagya Behera
BDO
Parajang Block