

**Estimate Abstract**

**OD/366/3513/120431/427476/00071608 : Const of CC Road at Deobandha of Phtaki GP  
Block : Chandahandi, Gram Panchayat : Phatki  
Created By:Nilakantha Pattnaik**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	10.8	Cubic Meter	240.77592	2600.379936
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	21	Cubic Meter	515.507232	10825.651872
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	30	Cubic Meter	5565.3699528	166961.098584
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	10.92	Cubic Meter	6952.3928326	75920.129731992

<b>Total Amount:</b>	256307.26012399
----------------------	-----------------

Provision for Contingency (+) @	692
Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	259999.26012399
----------------------	-----------------

<b>Grand Net Total Amount</b>	259999.26012399
-------------------------------	-----------------

**Nilakantha Pattnaik**  
**JE**  
**Chandahandi Block**

**Bhagaban Behera**  
**AEE**  
**Chandahandi Block**

**CHAINU GOND**  
**BDO**  
**Chandahandi Block**