

**Estimate Abstract**

**OD/370/3557/121253/426511/00072923 : Construction of CC road at Thota street at Sana Chandili  
Block : Rayagada, Gram Panchayat : Chandili  
Created By:T Someswar Rao**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	62.4	Cubic Meter	240.77592	15024.417408
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	16.575	Cubic Meter	647.009232	10724.1780204
3	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	19.5	Square Meter	216.23489289764	4216.580411504
4	<b>Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	29.325	Cubic Meter	5031.48320742	147548.24505759
5	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	17.55	Cubic Meter	6752.44342954	118505.38218843

<b>Total Amount:</b>	296018.80308592
----------------------	-----------------

Provision for Contingency (+) @	3000
Display Citizen Board (+) @	981

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	299999.80308592
----------------------	-----------------

<b>Grand Net Total Amount</b>	299999.80308592
-------------------------------	-----------------

**T Someswar Rao**  
**JE**  
**Rayagada Block**

**SAMEER KUMAR RATH**  
**AEE**  
**Rayagada Block**

**SHRI SUJIT KUMAR MISHRA**  
**BDO**  
**Rayagada Block**