

Estimate Abstract

**OD/363/3478/119902/00076809 : Construction of CC and Paver block road at Nua Dombo Street
Block : Pottangi, Gram Panchayat : Gangarajpur
Created By:KARTIK KULDIP**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	12.696	Cubic Meter	240.77592	3056.89108032
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	51.045	Cubic Meter	1320.275232	67393.44921744
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	8.82	Cubic Meter	5977.8041598	52724.232689436
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	130.96	Square Meter	217.49688418084	28483.391952323
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	16.435	Cubic Meter	7439.9749786	122275.98877329
6	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	333	Square Meter	645.903	215085.699

Total Amount:	489019.65271281
----------------------	-----------------

Provision for Contingency (+) @	4500
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	1479
Provision for survey investigation and quality control (+) @	

Total Amount:	499998.65271281
----------------------	-----------------

Grand Net Total Amount	499998.65271281
-------------------------------	-----------------

KARTIK KULDIP
JE
Pottangi Block

ER TOPHAN KUMAR NAYAK
AEE
Pottangi Block

RAMKRISHNA NAYAK
BDO
Pottangi Block