

**Estimate Abstract**

**OD/363/3471/119809/429995/00068767 : Construction of Paver Block Road at Paraja Street Mathalput  
Block : Koraput, Gram Panchayat : Mathalput  
Created By:SWARNAPRAVA MOHANTY**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	44.55	Cubic Meter	240.77592	10726.567236
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	26.4	Cubic Meter	1012.932232	26741.4109248
3	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	20.1	Cubic Meter	7092.7568756	142564.41319956
4	<b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	238.10445	Square Meter	636.774	151618.7230443
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	61.6	Square Meter	216.23489289764	13320.069402495

<b>Total Amount:</b>	344971.18380715
----------------------	-----------------

Provision for Contingency (+) @	3800
---------------------------------	------

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	26228
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	379999.18380715
----------------------	-----------------

<b>Grand Net Total Amount</b>	379999.18380715
-------------------------------	-----------------

**SWARNAPRAVA MOHANTY**  
**JE**  
**Koraput Block**

**PHAKIR MOHAN PRADHAN**  
**AEE**  
**Koraput Block**

**Dr. DEBASIS GOUDA**  
**BDO**  
**Koraput Block**