

Estimate Abstract

**OD/356/3396/118301/401887/00069234 : CONST OF CC ROAD FROM RAMESWAR TEMPLE TO MANIKA CHHAK
AUNRI**

**Block : Binjharpur, Gram Panchayat : Anuri
Created By:Karunasindhu Parida**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	3.35	Cubic Meter	240.77592	806.599332
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	28.475	Cubic Meter	787.298232	22418.3171562
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	48.982	Cubic Meter	6750.15887216	330636.28187614
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	53.6	Square Meter	216.23489289764	11590.190259314
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	20.636	Cubic Meter	8199.77144792	169210.48359928

Total Amount:	534661.87222293
----------------------	-----------------

Provision for Contingency (+) @	5346.6187222293
---------------------------------	-----------------

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	4991
Provision for survey investigation and quality control (+) @	

Total Amount:	549999.49094516
----------------------	-----------------

Grand Net Total Amount	549999.49094516
-------------------------------	-----------------

Karunasindhu Parida
JE
Binjharpur Block

ANANTA CH SETHY
AEE
Binjharpur Block

Akash Pattnaik
BDO
Binjharpur Block