

Estimate Abstract

**OD/367/3523/120590/406194/00069890 : DEVL.OF MAA BRAHAMNI DEVI COMMUNITY CENTER, BORAGOAN
Block : Bhapur, Gram Panchayat : Baigunia
Created By:Dillip Udalin**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	83.83	Square Meter	190.5435205504	15973.26332774
2	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	3.5225	Cubic Meter	6971.46110336	24556.971736586
3	Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	83.83	Square Meter	71.83248932951	6021.7175804928
4	Painting : AR0920 (Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)) : Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	83.83	Square Meter	94.7400035875	7942.0545007401
5	Other Building Items. : AR1902 (cement based wall putty (water based)) : Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.complete. and as per the direction of Engineer in Charge.			
	120.68	Square Meter	79.21834	9560.0692712
6	Flooring : AR0816a (Fixing Marble Tiles in floor, treads or steps and landing of minimum 16 mm thick, dunguri Variety Up to 0.10 Sqm Above 0.10 Sqm. to 0.40 Sqm on a 25mm thick bed of cement mortar 1:1) : Fixing Marble Tiles in floor, treads or steps and landing of minimum 16 mm thick, dunguri Variety Up to 0.10 Sqm Above 0.10 Sqm. to 0.40 Sqm on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the marble tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.			
	140.9	Square Meter	1455.3787020594	205062.85912017

7	Painting : AR0901ci (Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces(Outer surface)) : Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	125.6975	Square Meter	68.98780412951	8671.5945095691
8	Painting : AR0918ca (Finishing wall two coats with weather coat with one coat oilbound Primer) : Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	125.6975	Square Meter	156.85349521701	19716.09221504
9	Other Building Items. : AR1911 (Stainless steel of 304 grade in hand railing using 50mm dia of 2mm) : Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost,conveyance, taxes of all materials, labour,T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge			
	15.544799502566	Meter	3129.0244276074	48640.057365788

Total Amount:	346144.67962733
----------------------	-----------------

Provision for survey investigation and quality control (+) @	
Display Citizen Board (+) @	2500
Provision for Contingency (+) @	
Provision for EI Work (+) @	
Provision for PH Work (+) @	
Any Other Lumpsum (+) @	1355

Total Amount:	349999.67962733
----------------------	-----------------

Grand Net Total Amount	349999.67962733
-------------------------------	-----------------

Dillip Udalin
JE
Bhapur Block

Ritimukta Swain
AEE
Bhapur Block

SARADA PRASANNA PANDA
BDO
Bhapur Block