

Estimate Abstract

**OD/348/3324/116662/394508/00075378 : MAINTENANCE OF PANAKHA PRIMARY SCHOOL
Block : Bhandaripokhari, Gram Panchayat : Tealnga
Created By:Sagarika Jena**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.2954575	Cubic Meter	640.706832	2111.4221348156
2	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	2.82717	Cubic Meter	5691.08094206	16089.653306964
3	Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) : 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	11.9992	Square Meter	168.3585565212	2020.1679914092
4	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	1	Quintal	8413.975185	8413.975185
5	R.C.C. Work : AR0404A (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)			
	1.38199088	Cubic Meter	5875.9525506462	8120.5128363058
6	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	1.06125	Cubic Meter	7160.25362222	7598.819156581

7	Masonry Brick Work : AR0603bi (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	5.63736	Cubic Meter	5122.975874208	28880.059274225
8	Painting : AR0901b (Priming one coat in inner surface with primer of approved quality over iron work.) : Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	11.7054	Square Meter	66.11573166851	773.91108547258
9	Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	100.332	Square Meter	71.83248932951	7207.0973194084
10	Painting : AR0903i (Painting two coats of enamel paint in outer surface paint (outer surface)) : Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	7.315875	Square Meter	164.22772665202	1201.4695197203
11	Plastering : AR1004i (12mm thick cement plaster (1:6) over Brick work in outside.) : 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	44.592	Square Meter	168.3585565212	7507.4447523934
12	Dismantling : AR1603 (Dismantling brick or stone masonry under 3m.) : Dismantling brick or stone masonry in lime or cement mortar under 3m. height including stacking the useful materials for reuse and removing the debris within 50m. Lead and as per direction of Engineer-in-Charge.			
	5.094	Cubic Meter	1401.5088339223	7139.2860000002
13	Pile Foundation : AR1501a (Single under reamed pile foundation 375 mm dia and 6.0 meter long with RCC M20 using 12mm size black hard granite (Crusher broken) stone chips.) : Single under-reamed pile foundation with RCC M-20 using 12mm size black granite (Crusher broken) stone chips including cost of boring and including the labour charges, convenience, royalty, taxes of all materials, labour and T&P required for the work etc. but excluding the cost of M.S./Tor steel complete and as per direction of Engineer-in charge. (375mm dia and 6.0 meter long).			
	4	Number	7561.0674911094	30244.269964438
14	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	2.90075	Cubic Meter	240.77592	698.43074994

15	Painting : AR0918Ai (Finishing wall one coat with weather coat) : Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.			
	100.332	Square Meter	57.0910986525	5728.0641100026
16	Other Building Items. : AR1901A (Supplying, fitting and fixing vitrified tile in floors of size 600mm x 600mm of approved make conforming to IS :13755 with application of polymer modified quick set cement based water resistant adhesive conforming to IS :15477 of 3mm thick bed and fillin) : Supplying, fitting and fixing Vitrified Tile 600mmx600mm Plain (Ivory) of approved make conforming to IS :13755 with application of polymer modified quick set cement based water resistant adhesive conforming to IS :15477 of 3mm thick bed and filling joints with white cement of approved quality including cost of all materials, labour ,T&P,etc. required for the work all complete as per direction of Engineer-in-Charge(for repair work only)			
	5.574	Square Meter	2107.923759573	11749.56703586

Total Amount:	145484.15042254
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	1500
Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	149984.15042254
----------------------	-----------------

Grand Net Total Amount	149984.15042254
-------------------------------	-----------------

Sagarika Jena
JE
Bhandaripokhari Block

HRUDANANDA
AEE
Bhandaripokhari Block

BDOBhandaripokhari
BDO
Bhandaripokhari Block