

Estimate Abstract

**OD/361/3452/119456/385948/00068174 : CONST. OF CC / PAVER ROAD FROM MAJHI SAHI TO APURBA
BANDHA**

**Block : Kendujhar Sadar, Gram Panchayat : Kandaraposi
Created By:Ranjan Kumar Swain**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4.0704833664	Cubic Meter	240.77592	980.07437738966
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	8.9632866048	Cubic Meter	1146.009832	10272.014576135
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.5220203056	Cubic Meter	6232.13356674	127895.97160385
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	18.50219712	Cubic Meter	7686.55797238	142218.21077928
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	50.5856835	Square Meter	216.23489289764	10938.389853776
Total Amount:				292304.66119043
Provision for Contingency (+) @				3000

Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	1694.34
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.00119043
----------------------	-----------------

Grand Net Total Amount	299999.00119043
-------------------------------	-----------------

Ranjan Kumar Swain
JE
Kendujhar Sadar Block

Sabyasachi Pradhan
AEE
Kendujhar Sadar Block

Binod Chandra Panda
BDO
Kendujhar Sadar Block