

Estimate Abstract

**OD/365/3506/120337/389150/00063178 : Improvement of C.C. road from PWD road to Bark Sahi at Mahulia GP
Block : Samakhunta, Gram Panchayat : Mahulia
Created By:PRASANTA KUMAR PRADHAN**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	2.85	Cubic Meter	240.77592	686.211372
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.34625	Cubic Meter	1096.832932	4767.110130705
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	11.5425	Cubic Meter	6311.4192192	72849.556337616
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	8.265	Square Meter	216.23489289764	1787.181389799
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	7.82325	Cubic Meter	7836.0394894	61303.295935449

Total Amount:	141393.35516557
----------------------	-----------------

Provision for Contingency (+) @	1413.9335516557
Display Citizen Board (+) @	3000

Any Other Lumpsum (+) @	1192.5
Provision for survey investigation and quality control (+) @	
Total Amount:	146999.78871722
Grand Net Total Amount	146999.78871723

PRASANTA KUMAR PRADHAN
JE
Samakhunta Block

SUVENDU NAIK
AEE
Samakhunta Block

MUNA SETHI
BDO
Samakhunta Block