

Estimate Abstract

**OD/369/3540/120957/409162/00068065 : CONSTRUCTION OF ROAD FROM NARENDRAPUR SCHOOL TO HARISAHDEV PITHA C.C ROAD
Block : Kakat Pur, Gram Panchayat : Jaleswarpada
Created By:RAJESH KUMAR ROUT JE**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	13.3224	Cubic Meter	240.77592	3207.713116608
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	26.6448	Cubic Meter	458.401832	12214.025133274
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	26.6448	Cubic Meter	6293.03133696	167676.56136703
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	29.12	Square Meter	216.23489289764	6296.7600811793
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	19.9836	Cubic Meter	7738.99829752	154653.04637832

Total Amount:	344048.10607641
----------------------	-----------------

Provision for Contingency (+) @	
---------------------------------	--

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	951.8
Provision for survey investigation and quality control (+) @	

Total Amount:	349999.90607641
----------------------	-----------------

Grand Net Total Amount	349999.90607641
-------------------------------	-----------------

RAJESH KUMAR ROUT JE
JE
Kakat Pur Block

SANTOSH KUMAR SETHI
AEE
Kakat Pur Block

PuriKakatPurBDO
BDO
Kakat Pur Block