

Estimate Abstract

**OD/346/3307/116279/392870/00072725 : Const of CC Road from Dana Chhaka to Nimakali VillBoita
Block : Remuna, Gram Panchayat : Maharajpur
Created By:DHARMENDRA JENA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	7.8705	Cubic Meter	240.77592	1895.02687836
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	34.6302	Cubic Meter	1261.432632	43683.664332686
3	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	27.54675	Cubic Meter	7772.40764312	214104.57024312
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	96.195	Square Meter	216.4557413722	20821.960041299
5	miscellaneous : ARM260 (Laying and fixing in position R.C.C. spun pipes with collars jointed with cement mortar 1:3 complete excluding cost of spun pipes and collars 450mm dia R.C.C. pipe. (Other miscellaneous items) and as directed by Engineer-in-Charge.) : Laying and fixing in position R.C.C. spun pipes with collars jointed with cement mortar 1:3 complete excluding cost of spun pipes and collars 450mm dia R.C.C. pipe. (Other miscellaneous items) and as directed by Engineer-in-Charge.			
	48	Meter	30.32	1455.36
6	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	36.2043	Cubic Meter	6130.42606376	221947.78434019

Total Amount:	503908.36583565
----------------------	-----------------

Provision for Contingency (+) @	5500
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	35591
Provision for survey investigation and quality control (+) @	

Total Amount:	549999.36583565
----------------------	-----------------

Grand Net Total Amount	549999.36583565
-------------------------------	-----------------

DHARMENDRA JENA
JE
Remuna Block

AJAY KUMAR BEHERA
AEE
Remuna Block

Sourav Sarthak Mohapatra
BDO
Remuna Block