

Estimate Abstract

**OD/361/3449/119403/387074/00071675 : Repair and Maintenance of Govt. Primary School at Bareswar
Block : Hatadihi, Gram Panchayat : Panchugochia
Created By:PRAFULLA CHANDRA BEHERA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	miscellaneous : ARM122 (Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge.) : Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge.			
	274.905	Square Meter	5.12	1407.5136
2	Dismantling : AR1621 (Removing old grading plaster from roof) : Removing old grading plaster from roof slab, cleaning the surface, lowering and removing the debris within 50m lead and as per direction of Engineer-in-Charge.			
	74.86	Square Meter	77.77	5821.8622
3	Dismantling : AR1613 (Removing old lime or cement plaster) : Removing old lime or cement plaster from walls including raking out joints 12 mm deep and removing the debris within 50m lead and as per direction of Engineer-in-Charge.			
	89.4	Square Meter	50.174193548387	4485.5729032258
4	Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) : 12mm thick cement plaster (1:6) over Brick work in inside including raking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp. and as per direction of Engineer-in-charge.			
	89	Square Meter	175.1688860464	15590.03085813
5	Painting : AR0922 (Finishing wall two coats with distemper of approved shades on new work (Inside)) : Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	277.75	Square Meter	78.835517175	21896.564895356
6	Painting : AR0918Ai (Finishing wall one coat with weather coat) : Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.			
	133.44	Square Meter	57.0910986525	7618.2362041896
7	Painting : AR0920k (Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)(For Repair and maintenance)) : Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)(For Repair and maintenance)			

140.71	Square Meter	95.2170467875	13397.990653469
8	Painting : AR0901b (Priming one coat in inner surface with primer of approved quality over iron work.) : Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.		
	27.18	Square Meter	66.11573166851
9	Painting : AR0903i (Painting two coats of enamel paint in outer surface paint (outer surface)) : Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)		
	27.18	Square Meter	164.22772665202
10	Concrete : AR0318 (4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken)) : 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&P required for the work etc. complete as per specification and direction of Engineer-in charge. (Old Work)		
	74.86	Square Meter	759.8724000696
11	Dismantling : AR1625 (Dismantling and removing R.C.C. Chajja, Shelves, fins and parapet) : Dismantling and removing R.C.C. Chajja, Shelves, fins and parapet including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.		
	9.7199999973	Square Meter	175.60967741935
12	R.C.C. Work : AR0404Ag (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)		
	0.243	Cubic Meter	12810.292307283

Total Amount:	138182.38147544
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	9500
Provision for Contingency (+) @	1381.8238147544
Display Citizen Board (+) @	935.6
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	149999.8052902
----------------------	----------------

Grand Net Total Amount	149999.80529019
-------------------------------	-----------------

PRAFULLA CHANDRA BEHERA
JE
Hatadihi Block

MADAN MOHAN BEHERA
AEE
Hatadihi Block

RANJAN KUMAR PARIDA
BDO
Hatadihi Block