

Estimate Abstract

**OD/370/3557/121261/426389/00073247 : Const of CC Road at Kasili
Block : Rayagada, Gram Panchayat : Kampamaligam
Created By:T Someswar Rao**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	100.225	Cubic Meter	240.77592	24131.766582
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	34.2	Cubic Meter	562.876232	19250.3671344
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	41.8	Cubic Meter	5135.06439372	214645.6916575
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	28.5	Square Meter	216.49140300164	6170.0049855467
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	25.65	Cubic Meter	6717.43017364	172302.08395387

Total Amount:	436499.91431331
----------------------	-----------------

Provision for Contingency (+) @	9000
Display Citizen Board (+) @	3500

Any Other Lumpsum (+) @	1000
Provision for survey investigation and quality control (+) @	

Total Amount:	449999.91431331
----------------------	-----------------

Grand Net Total Amount	449999.91431331
-------------------------------	-----------------

T Someswar Rao
JE
Rayagada Block

SAMEER KUMAR RATH
AEE
Rayagada Block

SHRI SUJIT KUMAR MISHRA
BDO
Rayagada Block