

Estimate Abstract

**OD/370/3555/121229/427126/00073789 : Construction of C.C road at RD road to Community Hall,Duriguda
Block : Padmapur, Gram Panchayat : Jatili
Created By:MANMOHAN SINGH**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	40.5	Cubic Meter	240.77592	9751.42476
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	19.98	Cubic Meter	855.372232	17090.33719536
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	30.51	Cubic Meter	5258.62422842	160440.62520909
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	14.985	Cubic Meter	6990.21227654	104748.33096395

Total Amount:	292030.71812841
----------------------	-----------------

Provision for Contingency (+) @	2969
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.71812841
----------------------	-----------------

Grand Net Total Amount	299999.71812841
-------------------------------	-----------------

MANMOHAN SINGH
JE
Padmapur Block

SIMANCHAL DASH
AEE
Padmapur Block

KURESH CHANDRA JANI
BDO
Padmapur Block