

Estimate Abstract

**OD/369/3536/120885/409251/00076762 : CONSTRUCTION OF COMMUNITY CUM CULTURAL CENTRE AT SRI
RAM TEMPLE NUAGARH
Block : Astaranga, Gram Panchayat : Nuagarh
Created By:RASMIREKHA SAHOO**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	R.C.C. Work : AR0404Aa (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)			
	6.5258	Cubic Meter	6908.7184368057	45084.914774907
2	R.C.C. Work : AR0404Ab (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)			
	3.141	Cubic Meter	7665.5405619474	24077.462905077
3	R.C.C. Work : AR0404Ac (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)			
	8.59225	Cubic Meter	14964.471824126	128578.48303085
4	R.C.C. Work : AR0404Ag (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)			
	6.7918875	Cubic Meter	13210.602841196	89724.928304584
5	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	25.48	Quintal	7947.1441455	202493.23282734

Total Amount:	489959.02184275
----------------------	-----------------

Provision for survey investigation and quality control (+) @	
Display Citizen Board (+) @	
Provision for Contingency (+) @	5000
Provision for EI Work (+) @	
Provision for PH Work (+) @	
Any Other Lumpsum (+) @	5000

Total Amount:	499959.02184275
----------------------	-----------------

Grand Net Total Amount	499959.02184275
-------------------------------	-----------------

RASMIREKHA SAHOO
JE
Astaranga Block

SANTOSH KUMAR SETHI
AEE
Astaranga Block

SASMITA BEHERA
BDO
Astaranga Block