

Estimate Abstract

**OD/365/3487/120066/390575/00066286 : REPAIR AND MAINTENANCE OF GOVT. PS TIKARPADA
Block : Badasahi, Gram Panchayat : Uthaninuagaon
Created By:NARAYAN BESHRA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	1.66075	Cubic Meter	6203.3051933	10302.139099773
2	Flooring : AR0802ii (2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.			
	20.075	Square Meter	375.655823186	7541.290650459
3	Masonry Brick Work : AR0603bi (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	7.072	Cubic Meter	5254.33857824	37158.682425313
4	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	51.64675	Square Meter	257.32457911	13289.978206149
5	Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) : 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	57.74675	Square Meter	180.866293986	10444.440662236
6	Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	114.6255	Square Meter	71.84257680551	8234.99128762

7	Painting : AR0918fk (Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside)(For repair and maintenance) .) : Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint and Brushes required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).			
	116.7604	Square Meter	89.1455454125	10408.669540582
8	Painting : AR0903b (Painting two coats of enamel paint with a coat of red oxide primer over iron surface) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.			
	13.753125	Square Meter	230.36495425153	3168.2380114406
9	Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)			
	18.6085	Square Meter	1027.857585881	19126.887886867
10	Flooring : AR0817aa (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.			
	2.64	Square Meter	1547.595857866	4085.6530647662
11	Concrete : AR0318 (4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken)) : 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&P required for the work etc. complete as per specification and direction of Engineer-in charge. (Old Work)			
	28.3128	Square Meter	767.802967479	21738.651857639

Total Amount:	145499.62269285
----------------------	-----------------

Provision for PH Work (+) @	0
Provision for EI Work (+) @	0
Provision for Contingency (+) @	1500
Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	0

Provision for survey investigation and quality control (+) @	0
--	---

Total Amount:	149999.62269285
----------------------	-----------------

Grand Net Total Amount	149999.62269285
-------------------------------	-----------------

NARAYAN BESHRA
JE
Badasahi Block

DASHARATH MOHANTA
AEE
Badasahi Block

BANAJA DAS
BDO
Badasahi Block