

Estimate Abstract

**OD/373/3574/121540/384097/00068839 : Construction of Cement Concrete Road from Promod House to Junabandh Gargadbahal
Block : Bargaon, Gram Panchayat : Dandajamira
Created By:DEBASISH HOTA JE**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	35.5695	Cubic Meter	240.77592	8564.27908644
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.785	Cubic Meter	856.382232	18656.28692412
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	24.677	Cubic Meter	5705.20634352	140787.37693904
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	28.7	Square Meter	216.39264180804	6210.4688198907
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	16.33875	Cubic Meter	7155.97910224	116919.75355672

Total Amount:	291138.16532622
----------------------	-----------------

Provision for Contingency (+) @	2911.3816532622
---------------------------------	-----------------

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	950
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.54697948
----------------------	-----------------

Grand Net Total Amount	299999.54697948
-------------------------------	-----------------

DEBASISH HOTA JE
JE
Bargaon Block

SUNIL MURMU
AEE
Bargaon Block

BDO Bargaon
BDO
Bargaon Block