

Estimate Abstract

OD/363/3468/119753/428318/00069845 : INFRASTRUCTURE DEVELOPMENT NEAR TARABHATTA POLICE STATION

**Block : Borigumma, Gram Panchayat : Narigam
Created By:SMT SABITRI MAJHI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Other Building Items. : AR1903 (False ceiling) : Providing fitting and fixing of false ceiling with Aluminium anodised T Section No.3215 with 2'-0" center to center, L section No.1705 upto 15 micron on 4 walls to be fixed by means of steel screw and P.V.C.plug and the Aluminium grid 2'-0"x2'-0"with 12mm thick Prelaminated Novapan board suspended from ceiling etc. complete and as per direction of engineer in charge.			
	39.06	Square Meter	1438.4336756452	56185.219370702
2	Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	76.8	Square Meter	71.84257680551	5517.5098986632
3	Painting : AR0920 (Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)) : Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	76.8	Square Meter	94.7676397125	7278.15472992
4	Painting : AR0918g (Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work .(Outside)) : Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)			
	76.8	Square Meter	156.87265501801	12047.819905383
5	Painting : AR0903b (Painting two coats of enamel paint with a coat of red oxide primer over iron surface) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.			
	10.08	Square Meter	230.03789605153	2318.7819921994
6	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.906	Cubic Meter	5558.18608944	21710.274865353

7	Flooring : AR0817aa (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.			
	2.516	Square Meter	1531.776664691	3853.9500883626
8	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	3.906	Cubic Meter	7051.62792628	27543.65868005
9	Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)			
	39.06	Square Meter	1011.9613643894	39527.21089305
10	Dismantling : AR1612 (Dismantling and removing 2.5 cm. thick artificial stone flooring) : Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.			
	44.64	Square Meter	100.34838709677	4479.5519999998
11	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	14	Square Meter	630.9195	8832.873

Total Amount:	189295.00542368
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	6000
Provision for Contingency (+) @	1892.9500542368
Display Citizen Board (+) @	2800
Any Other Lumpsum (+) @	

Provision for survey investigation and quality control (+) @	
--	--

Total Amount:	199987.95547792
----------------------	-----------------

Grand Net Total Amount	199987.95547792
-------------------------------	-----------------

SMT SABITRI MAJHI
JE
Borigumma Block

Prakash Kumar Pradhan
AEE
Borigumma Block

SUKANTA KUMAR PATNAIK
BDO
Borigumma Block