

**Estimate Abstract**

**OD/365/3500/120253/389365/00077429 : Const. of CC road from PMGSY road to Dasha Sahi  
Block : Kuliana, Gram Panchayat : Kuchei  
Created By:SRIMANTA SETHI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	5.73	Cubic Meter	240.77592	1379.6460216
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	19.96875	Cubic Meter	1089.884132	21763.623760875
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	24.26625	Cubic Meter	6283.5092428	152477.2061631
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	13.365	Cubic Meter	7804.6710306	104309.42832397
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	51.3	Square Meter	216.23489289764	11092.850005649

<b>Total Amount:</b>	291022.75427519
----------------------	-----------------

Provision for Contingency (+) @	3000
Display Citizen Board (+) @	4000

Any Other Lumpsum (+) @	1977
Provision for survey investigation and quality control (+) @	
<b>Total Amount:</b>	299999.75427519
<b>Grand Net Total Amount</b>	299999.75427519

**SRIMANTA SETHI**  
**JE**  
**Kuliana Block**

**PAPU BHUYAN**  
**AEE**  
**Kuliana Block**

**Jitendra Murmu**  
**BDO**  
**Kuliana Block**