

Estimate Abstract

**OD/352/3349/117253/402631/00069182 : Repair & Maintenance of Mrudanga Nua sahi-1 AWC Building
Block : Bhuban, Gram Panchayat : Mrudanga
Created By:Girish Kumar Parida**

SI No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Painting : AR0917hk (Finishing wall with one coat weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work (Outside)(For repair and maintenance).) : Finishing wall with one coat weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).			
	115.7106865	Square Meter	131.98321246371	15271.868120651
2	Painting : AR0903b (Painting two coats of enamel paint with a coat of red oxide primer over iron surface) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.			
	24.66295941	Square Meter	230.37570221703	5681.7465928289

Total Amount:	20953.61471348
----------------------	----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	450
Display Citizen Board (+) @	200
Any Other Lumpsum (+) @	23395
Provision for survey investigation and quality control (+) @	

Total Amount:	44998.61471348
----------------------	----------------

Grand Net Total Amount	44998.61471348
-------------------------------	----------------

Girish Kumar Parida
JE
Bhuban Block

Ranjit Behera
AEE
Bhuban Block

Ayushi Mohapatra
BDO
Bhuban Block