

**Estimate Abstract**

**OD/363/3471/119803/428971/00069423 : Construction of paver block road inside Salmanguda village  
Block : Koraput, Gram Panchayat : Kerenga  
Created By:P Santosh Kumar Patro**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	9.6	Cubic Meter	240.77592	2311.448832
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	25.5	Cubic Meter	1194.227232	30452.794416
3	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	11.04	Cubic Meter	7469.50517478	82463.337129571
4	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	48	Square Meter	216.70813962884	10401.990702184
5	<b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	231	Square Meter	642.159	148338.729

<b>Total Amount:</b>	273968.30007976
----------------------	-----------------

Provision for Contingency (+) @	3000
---------------------------------	------

Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	20031
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	299999.30007976
----------------------	-----------------

<b>Grand Net Total Amount</b>	299999.30007976
-------------------------------	-----------------

**P Santosh Kumar Patro**  
**JE**  
**Koraput Block**

**PHAKIR MOHAN PRADHAN**  
**AEE**  
**Koraput Block**

**Dr. DEBASIS GOUDA**  
**BDO**  
**Koraput Block**