

**Estimate Abstract**

**OD/363/3475/119864/428859/00069697 : Const. of Paver block road at D. Panchada UPS  
Block : Laxmipur, Gram Panchayat : Panchada  
Created By:RANJIT KHOSLA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	20.745	Cubic Meter	240.77592	4994.8964604
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	28.875	Cubic Meter	647.009232	18682.391574
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	24.2025	Cubic Meter	5843.26050844	141421.51245552
4	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	138.3	Square Meter	216.39264180804	29927.102362052
5	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	4.875	Cubic Meter	7305.87805428	35616.155514615
6	<b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	383.95	Square Meter	625.905	240316.22475

<b>Total Amount:</b>	470958.28311659
----------------------	-----------------

Provision for Contingency (+) @	4709.5828311659
Display Citizen Board (+) @	4235
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	479902.86594775
----------------------	-----------------

<b>Grand Net Total Amount</b>	479902.86594775
-------------------------------	-----------------

**RANJIT KHOSLA**  
JE  
Laxmipur Block

**AEE**  
Laxmipur Block

**SABYASACHI BEHERA**  
BDO  
Laxmipur Block