

Estimate Abstract

**OD/352/3356/117411/402231/00073808 : NH 149 to Bisanali Sahi Main Road
Block : Parajang, Gram Panchayat : Akhuapal
Created By:Pinky behera**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0110 (Fine dressing of earth work in ordinary or hard soil in road formation) : Fine dressing of earth work in ordinary or hard soil in road formaton according to the direction of the department including cutting or filling earth upto 0.15m depth of surface.			
	347.828832	Square Meter	4.6662	1623.0388958784
2	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	6.15965156352	Cubic Meter	240.77592	1483.095772086
3	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	25.16251236096	Cubic Meter	1418.447232	35691.696008569
4	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	33.815356224	Cubic Meter	6156.02957184	208168.33289725
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	26.5045248	Cubic Meter	7569.02181808	200613.32648904
6	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	72.46434	Square Meter	216.23489289764	15669.318798798

Total Amount:	463248.80886162
----------------------	-----------------

Provision for Contingency (+) @	4750
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	2001
Provision for survey investigation and quality control (+) @	

Total Amount:	474999.80886162
----------------------	-----------------

Grand Net Total Amount	474999.80886162
-------------------------------	-----------------

Pinky behera
JE
Parajang Block

Rani panda
AEE
Parajang Block

Sauvagya Behera
BDO
Parajang Block