

Estimate Abstract

**OD/346/3309/116328/394014/00063276 : Maint. of road and Bridges from Saraswatipur incomplete CC road to Satyabrata Pati house , Saraswatipur
Block : Soro, Gram Panchayat : Saknar
Created By:Chandra Sekhar Mohapatra**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	1.4441568	Cubic Meter	240.77592	347.71818214426
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	6.35428992	Cubic Meter	1493.995232	9493.2788432257
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.79844672	Cubic Meter	6143.35926526	47908.659911948
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	4.813856	Cubic Meter	7586.32993962	36519.499897819
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	19.96299664	Square Meter	216.23489289764	4316.6964403663
Total Amount:				98585.853275504
Provision for Contingency (+) @				1000

Display Citizen Board (+) @	414.14
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	99999.993275504
----------------------	-----------------

Grand Net Total Amount	99999.993275504
-------------------------------	-----------------

Chandra Sekhar Mohapatra
JE
Soro Block

Nirmala Kanta Parida
AEE
Soro Block

Satyanath Naik
BDO
Soro Block