

**Estimate Abstract**

**OD/365/3503/120297/387725/00072696 : Construction of CC Drain from Suru Munda land to Arun Munda land at Kapili  
Block : Rairangpur, Gram Panchayat : Hatia  
Created By:PRASHANTA KUMAR DAS**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	86.66875	Cubic Meter	240.77592	20867.7480165
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	17.33375	Cubic Meter	1088.167132	18862.017024305
3	<b>Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) :</b> 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	238.98525	Square Meter	195.573308794	46739.136095461
4	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	204.8445	Square Meter	216.23489289764	44294.528518171
5	<b>Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	45.06775	Cubic Meter	5851.9196283	263732.85082832
6	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	3.813425	Cubic Meter	7620.3201746	29059.519461824

<b>Total Amount:</b>	423555.79994458
----------------------	-----------------

Display Citizen Board (+) @	3500
Any Other Lumpsum (+) @	1527.2
Provision for survey investigation and quality control (+) @	0
Provision for Contingency (+) @	0

<b>Total Amount:</b>	428582.99994458
----------------------	-----------------

<b>Grand Net Total Amount</b>	428582.99994458
-------------------------------	-----------------

**PRASHANTA KUMAR DAS**  
**JE**  
**Rairangpur Block**

**ANSHUMAN SAMAL**  
**AEE**  
**Rairangpur Block**

**Narayani Priyadarshini panda**  
**BDO**  
**Rairangpur Block**