

Estimate Abstract

**OD/346/3309/116314/393717/00062632 : Const. of cc road from Sanatan Mohapatra house to PMGSY road
Block : Soro, Gram Panchayat : Gopinathpur
Created By:Chandra Sekhar Mohapatra**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	2.9095512	Cubic Meter	240.77592	700.5498669671
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	12.80202528	Cubic Meter	1540.455232	19720.946822772
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	15.71157648	Cubic Meter	6014.16976126	94492.08816774
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	10.26484	Cubic Meter	7465.21477962	76629.235278435
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	31.93633528	Square Meter	216.23489289764	6905.7500388139

Total Amount:	198448.57017473
----------------------	-----------------

Provision for Contingency (+) @	2020
Display Citizen Board (+) @	1569.42

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	202037.99017473
----------------------	-----------------

Grand Net Total Amount	202037.99017473
-------------------------------	-----------------

Chandra Sekhar Mohapatra
JE
Soro Block

Nirmala Kanta Parida
AEE
Soro Block

Satyanath Naik
BDO
Soro Block