

Estimate Abstract

**OD/365/3503/120296/387675/00075103 : Const. Paver Block road from Halda School to Halda Jahira at Halda
Block : Rairangpur, Gram Panchayat : Halda
Created By:PRASHANTA KUMAR DAS**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	61.0357137	Cubic Meter	240.77592	14695.930118974
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	116.61864	Cubic Meter	693.661132	80893.8178347
3	Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	39.32457	Square Meter	191.497686094	7530.5641616415
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	173.40714	Square Meter	216.23489289764	37496.674345586
5	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.9222837	Cubic Meter	5599.4357883	122752.41991105
6	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	2.381445	Cubic Meter	7286.6447071	17352.7436045

7	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	244.712535	Square Meter	627.2907	153505.89737892

Total Amount:	434228.04735537
----------------------	-----------------

Provision for Contingency (+) @	0
Display Citizen Board (+) @	3500
Any Other Lumpsum (+) @	1771.95
Provision for survey investigation and quality control (+) @	0

Total Amount:	439499.99735537
----------------------	-----------------

Grand Net Total Amount	439499.99735537
-------------------------------	-----------------

PRASHANTA KUMAR DAS
JE
Rairangpur Block

ANSHUMAN SAMAL
AEE
Rairangpur Block

Narayani Priyadarshini panda
BDO
Rairangpur Block