

Estimate Abstract

**OD/370/3547/121114/425355/00073949 : CONSTN OF CC ROAD AT LELIBADI
Block : Bissamcuttack, Gram Panchayat : Hajaridang
Created By: BISWABHUSAN BEHERA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	21.6	Cubic Meter	240.77592	5200.759872
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	6	Cubic Meter	650.948232	3905.689392
3	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	21	Square Meter	216.23489289764	4540.9327508504
4	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	15.6	Cubic Meter	5032.75220172	78510.934346832
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	29.2	Cubic Meter	6769.35225364	197665.08580629

Total Amount:	289823.40216797
----------------------	-----------------

Provision for Contingency (+) @	3000
Display Citizen Board (+) @	5000

Any Other Lumpsum (+) @	2176
Provision for survey investigation and quality control (+) @	
Total Amount:	299999.40216797
Grand Net Total Amount	299999.40216797

BISWABHUSAN BEHERA
JE
Bissamcuttack Block

SRI RAMESH CHANDRA SAHU
AEE
Bissamcuttack Block

SRI SIBA PRASAD PATNAIK
BDO
Bissamcuttack Block