

Estimate Abstract

**OD/370/3556/121239/426775/00072158 : Const of CC road/ paver block at AWC Palkidanga
Block : Ramanaguda, Gram Panchayat : Gogupadu
Created By: BABULAL PALAI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4.5	Cubic Meter	240.77592	1083.49164
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	31.5	Cubic Meter	464.906232	14644.546308
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	28.5	Cubic Meter	5270.33447142	150204.53243547
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	16.8	Cubic Meter	6840.34372954	114917.77465627
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	38.4	Square Meter	216.23489289764	8303.4198872694

Total Amount:	289153.76492701
----------------------	-----------------

Provision for Contingency (+) @	2891.5376492701
Display Citizen Board (+) @	5000

Any Other Lumpsum (+) @	2954
Provision for survey investigation and quality control (+) @	
Total Amount:	299999.30257628
Grand Net Total Amount	299999.30257628

BABULAL PALAI
JE
Ramanaguda Block

HARE KRUSHNA PANDA
AEE
Ramanaguda Block

PRADYUMNA MANDAL
BDO
Ramanaguda Block