

**Estimate Abstract**

**OD/365/3498/120222/388830/00069108 : DRAINAGE SYSTEM AT DORI VILLAGE**

**Block : Karanjia, Gram Panchayat : Dori**

**Created By:RADHAGOBINDA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	34.6005	Cubic Meter	240.77592	8330.96721996
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	6.59025	Cubic Meter	854.513732	5631.459122313
3	<b>Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	19.31625	Cubic Meter	5619.648484	108550.53502907
4	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	78.78	Square Meter	216.39264180804	17047.412321637
5	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	2.2725	Cubic Meter	7386.882147	16786.689679058
6	<b>Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) :</b> 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	78.78	Square Meter	193.46352343	15241.056375815

<b>Total Amount:</b>	171588.11974785
----------------------	-----------------

Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	2208.1
Provision for survey investigation and quality control (+) @	
Provision for Contingency (+) @	1785

<b>Total Amount:</b>	178581.21974785
----------------------	-----------------

<b>Grand Net Total Amount</b>	178581.21974785
-------------------------------	-----------------

**RADHAGOBINDA**  
**JE**  
**Karanjia Block**

**LOKANATH NAIK**  
**AEE**  
**Karanjia Block**

**PRADYUMNA KUMAR NAYAK**  
**BDO**  
**Karanjia Block**