

Estimate Abstract

**OD/363/3467/119729/429305/00074140 : PAVER BLOCK AT KATRAKUND NUA SAHI
Block : Boipariguda, Gram Panchayat : Ramagiri
Created By: Debabrat Sarkar**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	57.6	Cubic Meter	240.77592	13868.692992
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	50.4	Cubic Meter	581.258232	29295.4148928
3	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	21.6	Cubic Meter	6865.37099828	148292.01356285
4	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	432	Square Meter	623.952	269547.264
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	172.8	Square Meter	216.55039071844	37419.907516146

Total Amount:	498423.29296379
----------------------	-----------------

Provision for Contingency (+) @	576
---------------------------------	-----

Display Citizen Board (+) @	1000
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	499999.29296379
----------------------	-----------------

Grand Net Total Amount	499999.29296379
-------------------------------	-----------------

Debabrat Sarkar
JE
Boipariguda Block

Khiroda chandra Behara
AEE
Boipariguda Block

Subrat Kumar Sahu
BDO
Boipariguda Block