

Estimate Abstract

**OD/365/3488/120067/387559/00067620 : Repair & Maintenance of AWC Building at Gunduria
Block : Bahalda, Gram Panchayat : Anlajodi
Created By:ASWINI KUMAR MOHANTA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Dismantling : AR1612 (Dismantling and removing 2.5 cm. thick artificial stone flooring) : Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.			
	38.85667975	Square Meter	100.34838709677	3899.2051408482
2	Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)			
	38.85667975	Square Meter	1019.200622371	39602.752184471
3	Flooring : AR0817aa (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.			
	3.357049905	Square Meter	1541.926566771	5176.3244344956
4	Dismantling : AR1620 (Dismantling and removing 2.5 cm thick grading concrete from roof) : Dismantling and removing 2.5 cm thick grading concrete from roof slab cleaning the surface lowering and removing the debris within 50m lead and as per direction of Engineer-in-Charge.			
	49.5105914034	Square Meter	112.89193548387	5589.3464904809
5	Concrete : AR0318 (4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken)) : 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&P required for the work etc. complete as per specifaicaon and direction of Engineer-in charge. (Old Work)			
	49.5105914034	Square Meter	757.912924764	37524.717137346
6	Painting : AR0918cb (Finishing wall two coats with weather coat with one coat waterbound Primer) : Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	196.74532825	Square Meter	160.76701381363	31630.158904535

7	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.452809008	Cubic Meter	5883.3068428	20313.934863648
8	Iron Work : AR1704 (Iron Doors and windows fixing) : Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.			
	1.623	Quintal	15765.740055087	25587.796109406
9	Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) : 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	39.576678	Square Meter	172.502149676	6827.0620320349

Total Amount:	176151.29729727
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	15000
Provision for Contingency (+) @	2020
Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	5866
Provision for survey investigation and quality control (+) @	

Total Amount:	202037.29729727
----------------------	-----------------

Grand Net Total Amount	202037.29729727
-------------------------------	-----------------

ASWINI KUMAR MOHANTA
JE
Bahalda Block

MADAN MOHAN NAIK
AEE
Bahalda Block

MayurbhanjBahaldaBDO
BDO
Bahalda Block