

Estimate Abstract

**OD/367/3523/120606/406116/00071192 : Const. of Tikiripada Bramahani Devi Nutana Mandap
Block : Bhapur, Gram Panchayat : Sasana
Created By:Aishwarya Rajalaxmi Nath**

SI No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Masonry Brick Work : AR0603bi (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	22.6525	Cubic Meter	5074.267725712	114944.84965669
2	Plastering : AR1004i (12mm thick cement plaster (1:6) over Brick work in outside.) : 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	109.705	Square Meter	171.3312931168	18795.899511379
3	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	91.835	Square Meter	245.878048928	22580.210623303
4	Plastering : AR1026 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces (inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	52.38	Square Meter	159.3617997616	8347.3710715126
5	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	2.945953125	Cubic Meter	5324.19033984	15684.815169746
6	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	1.96396875	Cubic Meter	6826.66878808	13407.364166389

7	Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)			
	39.279375	Square Meter	996.3659083334	39136.630150643
8	Flooring : AR0817aa (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.			
	4.26375	Square Meter	1515.190315411	6460.3927073337
9	Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	136.39	Square Meter	71.83248932951	9797.2332196519
10	Painting : AR0901di (Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces(outer surface)) : Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	101.88	Square Meter	72.849606979355	7421.9179590567
11	Painting : AR0918f (Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside)) : Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)			
	101.88	Square Meter	87.8656910875	8951.7566079945
12	Painting : AR0920 (Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)) : Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	136.39	Square Meter	94.7400035875	12921.589089299
13	Iron Work : AR1704 (Iron Doors and windows fixing) : Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.			
	0.9585	Quintal	15973.749353087	15310.838754934
Total Amount:			293760.86868793	

Provision for survey investigation and quality control (+) @	
Display Citizen Board (+) @	3230
Provision for Contingency (+) @	3000
Provision for EI Work (+) @	
Provision for PH Work (+) @	
Any Other Lumpsum (+) @	

Total Amount:	299990.86868793
----------------------	-----------------

Grand Net Total Amount	299990.86868793
-------------------------------	-----------------

Aishwarya Rajalaxmi Nath
JE
Bhapur Block

Ritimukta Swain
AEE
Bhapur Block

SARADA PRASANNA PANDA
BDO
Bhapur Block