

**Estimate Abstract**

**OD/371/3563/121373/382251/00066855 : CONSTRUCTION OF PAVER BLOCK ROAD AT UPPERPADA DHAMA  
Block : Maneswar, Gram Panchayat : Dhama  
Created By:Ranjit Maharana**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	1.362746	Cubic Meter	7206.8019851	9821.0405779871
2	<b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	382.4351995	Square Meter	632.7858	241999.56366377

<b>Total Amount:</b>	251820.60424175
----------------------	-----------------

Provision for Contingency (+) @	1500
Display Citizen Board (+) @	4799
Any Other Lumpsum (+) @	41880
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	299999.60424175
----------------------	-----------------

<b>Grand Net Total Amount</b>	299999.60424175
-------------------------------	-----------------

**Ranjit Maharana**  
JE  
Maneswar Block

**TUSHAR KUMAR SAMAL**  
AEE  
Maneswar Block

**CHITTA RANJAN MALLIK**  
BDO  
Maneswar Block