

Estimate Abstract

**OD/367/3523/120606/907585/00071196 : Const. of Ragadipada Khela Padia Nutana Gruha and Water Supply
Block : Bhapur, Gram Panchayat : Sasana
Created By:Aishwarya Rajalaxmi Nath**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	12.1995	Cubic Meter	240.77592	2937.34583604
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	8.442	Cubic Meter	894.933932	7555.032253944
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.2799375	Cubic Meter	5324.19033984	17463.011552779
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	1.08675	Cubic Meter	6826.66878808	7418.8823054459
5	Masonry Brick Work : AR0603b (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	4.9225	Cubic Meter	5040.937725712	24814.015954817
6	Masonry Brick Work : AR0603bi (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	8.71875	Cubic Meter	5074.267725712	44241.271733552

7	R.C.C. Work : AR0404Aa (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)			
	0.432	Cubic Meter	5848.6290924633	2526.6077679441
8	R.C.C. Work : AR0404Ab (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)			
	0.8875	Cubic Meter	6605.451217605	5862.3379556244
9	R.C.C. Work : AR0404Ac (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)			
	1.67	Cubic Meter	13904.382479783	23220.318741238
10	R.C.C. Work : AR0404Ad (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)			
	0.5325	Cubic Meter	12512.913320994	6663.1263434293
11	R.C.C. Work : AR0404Ag (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)			
	1.9921875	Cubic Meter	12150.513496853	24206.101107012
12	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	7.2	Quintal	8641.0649283	62215.66748376
13	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			

42.157	Square Meter	245.878048928	10365.603847682	
14	Plastering : AR1026 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces (inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	10.8675	Square Meter	159.3617997616	1731.8643589092
15	Plastering : AR1004i (12mm thick cement plaster (1:6) over Brick work in outside.) : 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	53.7475	Square Meter	171.3312931168	9208.6286767952
16	Iron Work : AR1704 (Iron Doors and windows fixing) : Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.			
	1.34505	Quintal	15973.749353087	21485.49156737
17	Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	50.9625	Square Meter	71.83248932951	3660.7632374552
18	Painting : AR0901di (Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces(outer surface)) : Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	52.015	Square Meter	72.849606979355	3789.2723070312
19	Painting : AR0918f (Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside)) : Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)			
	52.015	Square Meter	87.8656910875	4570.3339219163
20	Plastering : AR1017 (20mm thick cement Plaster in CM (1:4) over masonry work in inside.) : 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	15.9375	Square Meter	268.7700033824	4283.521928907
21	Painting : AR0920 (Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)) : Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			

40.095	Square Meter	94.7400035875	3798.6004438408
--------	--------------	---------------	-----------------

Total Amount:	292017.79932549
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	3000
Display Citizen Board (+) @	4980
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	299997.79932549
----------------------	-----------------

Grand Net Total Amount	299997.79932549
-------------------------------	-----------------

Aishwarya Rajalaxmi Nath
JE
Bhapur Block

Ritimukta Swain
AEE
Bhapur Block

SARADA PRASANNA PANDA
BDO
Bhapur Block