

Estimate Abstract

**OD/360/3435/119066/396696/00100587 : CONST OF CC ROAD NEAR KOSIDA AGASTI MATHA
Block : Derabish, Gram Panchayat : Khamala
Created By:ABANI KUMAR MOHANTY**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0101aa (Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift) : Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum			
	4.665	Cubic Meter	179.18208	835.8844032
2	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.77	Cubic Meter	5962.91281676	129812.61202087
3	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	49.76	Square Meter	216.23489289764	10759.848270587
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	18.66	Cubic Meter	7479.27877712	139563.34198106
5	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.66	Cubic Meter	613.719632	11452.00833312
				Total Amount (A) : 292423.69500883

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.3000	-	3000
2	Display Citizen Board @ Rs.4576	-	4576
Additional Components Amount (F) : 7576			

Grand Total Amount (A + F) : 299999.69500883			
---	--	--	--

ABANI KUMAR MOHANTY
JE
Derabish Block

GOURAV SAHOO
AEE
Derabish Block

Namita Barik
BDO
Derabish Block