

**Estimate Abstract**

**OD/354/3380/117904/411502/00101990 : Improvement of road Badarala RD road to Tumbeswar mandir road at  
Ch. Sasan  
Block : Polosara, Gram Panchayat : Chirikpada Sasan  
Created By:Sarat Kumar Malla**

| Sl No | Quantity   | Unit        | Rate in (Rs.) | Amount (Rs.)                              |
|-------|--|-------------|---------------|---|
| 1     | <b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge   |             |               |   |
|       | 32.73879679488   | Cubic Meter | 240.77592     | 7882.7139179803                           |
| 2     | <b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.  |             |               |   |
|       | 16.36939839744   | Cubic Meter | 506.336432    | 8288.4227785463                           |
| 3     | <b>Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.           |             |               |   |
|       | 16.36939839744   | Cubic Meter | 4978.7734567  | 81499.526243322                           |
| 4     | <b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge. |             |               |   |
|       | 16.36939839744   | Cubic Meter | 6709.0724499  | 109823.4798097                            |
|       |  |             |               | <b>Total Amount (A) : 207494.14274955</b> |

| <b>Additional Components</b> |                                     |        |   |
|------------------------------|-------------------------------------|--------|---|
| #                            | Item Name                           | Remark | Amount (in Rs.)                                   |
| 1                            | Provision for Contingency @ Rs.1050 | -      | 1050  |
| 2                            | Display Citizen Board @ Rs.1455.85  | -      | 1455.85   |
|                              |                                     |        | <b>Additional Components Amount (F) : 2505.85</b> |

Grand Total Amount (A + F) : 209999.99274955

Sarat Kumar Malla  
JE  
Polosara Block

Laxmi Narayan Pattanayak  
AEE  
Polosara Block

SASI BHUSAN MAHAPATRO  
BDO  
Polosara Block