

Estimate Abstract

**OD/371/3561/121336/381860/00101972 : Construction of CC road from Buromal to Khejurpali
Block : Jujomura, Gram Panchayat : Ghenupali
Created By:PABITRA MOHAN LENKA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	53.518696	Cubic Meter	240.77592	12886.0132666
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	34.404876	Cubic Meter	549.907832	18919.510771389
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	37.271949	Cubic Meter	5664.3543463	211121.52631322
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	34.404876	Cubic Meter	7199.6589621	247703.37383334
				Total Amount (A) : 490630.42418455

Additional Components			
#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ Rs.5000	-	5000
2	Display Citizen Board @ Rs.4369	-	4369
3	Any Other Lumpsum @ Rs.0	-	0

4	Provision for survey investigation and quality control @ Rs.0	-	0
Additional Components Amount (F) : 9369			
Grand Total Amount (A + F) : 499999.42418455			

PABITRA MOHAN LENKA
JE
Jujomura Block

PRANABA KUMAR CHHURIA
AEE
Jujomura Block

RAJESH KUMAR EKKA
BDO
Jujomura Block