

**Estimate Abstract**

**OD/346/3302/275575/391780/00101571 : CONSTRUCTION OF CC ROAD FROM RAKHI GUEST HOUSE TO LAXMI  
KANTA BEHERA LAND VILL UDAYPUR  
Block : Bhograi, Gram Panchayat : Sahabajipur  
Created By: BANSHIDHAR JENA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0101aa (Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift) :</b> Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum			
	3.35182846752	Cubic Meter	179.18208	600.58759661345
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	14.338321747402	Cubic Meter	1268.765232	18191.964118333
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.746226318643	Cubic Meter	7180.30768126	134603.67283039
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	14.85810529632	Cubic Meter	8558.46907962	127162.63476029
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	43.6590402066	Square Meter	216.23489289764	9440.6078830879
<b>Total Amount (A) : 289999.46718872</b>				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.3000	-	3000
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.2000	Hiring Charges of vibrator	2000
<b>Additional Components Amount (F) : 10000</b>			
<b>Grand Total Amount (A + F) : 299999.46718872</b>			

**BANSHIDHAR JENA**  
**JE**  
**Bhograi Block**

**ANIL KUMAR BISWAL**  
**AEE**  
**Bhograi Block**

**Prasanta Kumar Moharana**  
**BDO**  
**Bhograi Block**