

Estimate Abstract

**OD/354/3380/117919/411713/00101472 : Repair/Renovation of AWC-III at Nimina
Block : Polosara, Gram Panchayat : Nimina
Created By:Indramani Sahu**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)			
	37.649	Square Meter	1003.528513375	37781.845000055
2	Flooring : AR0817aa (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.			
	6.267	Square Meter	1525.968612726	9563.2452959538
3	Painting : AR0901di (Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces(outer surface)) : Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	121.9	Square Meter	72.855030353548	8881.0282000975
4	Painting : AR0922 (Finishing wall two coats with distemper of approved shades on new work (Inside)) : Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	121.9	Square Meter	78.8505283	9611.87939977
5	Painting : AR0903i (Painting two coats of enamel paint in outer surface paint (outer surface)) : Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	24.39	Square Meter	164.23523221452	4005.6973137121
Total Amount (A) : 69843.695209589				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for PH Work @ Rs.25000	-	25000
2	Provision for EI Work @ Rs.16224.3	-	16224.3
3	Provision for Contingency @ Rs.1632	-	1632
4	Display Citizen Board @ Rs.500	-	500
5	Any Other Lumpsum @ Rs.50000	Door & Window	50000
Additional Components Amount (F) :			93356.3

Grand Total Amount (A + F) :			163199.99520959
-------------------------------------	--	--	------------------------

Indramani Sahu
JE
Polosara Block

Laxmi Narayan Pattanayak
AEE
Polosara Block

SASI BHUSAN MAHAPATRO
BDO
Polosara Block