

**Estimate Abstract**

**OD/370/3556/121244/426721/00099657 : Const of CC road at Sdhepaguda new street  
Block : Ramanaguda, Gram Panchayat : Nilamguda  
Created By:LADI RABINDRA KUMAR**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	26.675	Cubic Meter	240.77592	6422.697666
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.075	Cubic Meter	596.408232	11972.8952574
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	23.375	Cubic Meter	5297.83485242	123836.88967532
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	20.075	Cubic Meter	6879.13247654	138098.58446654
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	44	Square Meter	216.55039071844	9528.2171916114
				<b>Total Amount (A) : 289859.28425687</b>

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ 1%	-	2898.5928425687
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.2242.12	Any Item of Quntity Deviation if any...	2242.12
<b>Additional Components Amount (F) :</b>			<b>10140.712842569</b>

<b>Grand Total Amount (A + F) :</b>			<b>299999.99709944</b>
-------------------------------------	--	--	------------------------

**LADI RABINDRA KUMAR**  
**JE**  
Ramanaguda Block

**HARE KRUSHNA PANDA**  
**AEE**  
Ramanaguda Block

**PRADYUMNA MANDAL**  
**BDO**  
Ramanaguda Block