

**Estimate Abstract**

**OD/358/3414/118726/424112/00102860 : CONSTRUCTION OF CC ROAD AT PIPALGACH CHAK MAJHIPADA  
Block : Kalampur, Gram Panchayat : Kaklampur  
Created By:SUMANTA DANDAPATH**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102a (Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift)</b> : Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4.96	Cubic Meter	200.6466	995.207136
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed)</b> : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.39	Cubic Meter	561.462232	12009.67714248
3	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc)</b> : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	35.65	Square Meter	216.39264180804	7714.3976804566
4	<b>Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal)</b> : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	28.83	Cubic Meter	5310.69601466	153107.36610265
5	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum)</b> : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	16.9725	Cubic Meter	7041.50804342	119511.99526695
				<b>Total Amount (A) : 293338.64332853</b>

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ 1%	-	2933.3864332853
2	Display Citizen Board @ Rs.3727	-	3727
<b>Additional Components Amount (F) : 6660.3864332853</b>			

<b>Grand Total Amount (A + F) : 299999.02976182</b>			
---	--	--	--

**SUMANTA DANDAPATH**  
JE  
Kalampur Block

**PRAKASH CHANDRA SETHY**  
AEE  
Kalampur Block

**Bijaya kumar Mandngi**  
BDO  
Kalampur Block