

**Estimate Abstract**

**OD/346/3302/275565/924728/00101687 : CONSTRUCTION OF CC ROAD FROM GABARDHANPUR MISHRA  
CHHAKA TO SUNIL DAS HOUSE VIA JENA HOUSE VILL GABARDHANPUR  
Block : Bhograi, Gram Panchayat : Jaleswarpur  
Created By:SARADA PRASANNA MOHANTY**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0101aa (Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift) :</b> Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum			
	17.119204608	Cubic Meter	179.18208	3067.454689607
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	17.119204608	Cubic Meter	1032.061632	17668.074246274
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	17.119204608	Cubic Meter	6995.32739326	119754.44094517
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	17.119204608	Cubic Meter	8385.05005962	143545.38761896
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	28.50821458	Square Meter	216.23489289764	6164.4707264092
<b>Total Amount (A) : 290199.82822641</b>				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.3000	-	3000
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.1800	Vibrator	1800
4	Provision for survey investigation and quality control @ Rs.0	-	0
<b>Additional Components Amount (F) : 9800</b>			

<b>Grand Total Amount (A + F) : 299999.82822641</b>		
---	--	--

**SARADA PRASANNA MOHANTY**  
**JE**  
**Bhograi Block**

**PRAMOD KUMAR BEHERA**  
**AEE**  
**Bhograi Block**

**Prasanta Kumar Moharana**  
**BDO**  
**Bhograi Block**