

Estimate Abstract

**OD/371/3562/121359/381446/00105630 : Construction of CC road from Sankar Kisan (AWC 2) to Jai Kisan house
Block : Kuchinda, Gram Panchayat : Kuntara
Created By:Prakash Kumar Ping**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	30.6576	Cubic Meter	240.77592	7381.611844992
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	26.352	Cubic Meter	618.183832	16290.380340864
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	31.32	Cubic Meter	5597.1791958	175303.65241246
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicion and direction of Engineer-in charge.			
	26.28	Cubic Meter	7130.1786886	187381.09593641
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	21.6	Square Meter	216.23489289764	4670.673686589
				Total Amount (A) : 391027.41422131

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.3972.58	-	3972.58
2	Display Citizen Board @ Rs.5000	-	5000
Additional Components Amount (F) : 8972.58			

Grand Total Amount (A + F) : 399999.99422131			
---	--	--	--

Prakash Kumar Ping
JE
Kuchinda Block

Prangya Paramita Nayak
AEE
Kuchinda Block

Jayanta sahu
BDO
Kuchinda Block