

Estimate Abstract

**OD/363/3470/119778/429045/00066840 : CONSTRUCTION OF CC DRAIN AT PALLIGUDA
Block : Jeypore, Gram Panchayat : Anta
Created By:TARUN KUMAR NAIK**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	104.31	Cubic Meter	240.77592	25115.3362152
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	14.235	Cubic Meter	678.531332	9658.89351102
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	53.8521	Cubic Meter	5629.53777174	303162.43103752
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	254.04	Square Meter	216.64504006468	55036.505978031
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	8.322	Cubic Meter	7122.42227038	59272.798134102
				Total Amount (A) : 452245.96487587

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ 1%	-	4522.4596487587
2	Display Citizen Board @ Rs.3231.57	-	3231.57
Additional Components Amount (F) : 7754.0296487587			

Grand Total Amount (A + F) : 459999.99452463			
---	--	--	--

TARUN KUMAR NAIK
JE
Jeypore Block

BIJAYA KUMAR NANDA
AEE
Jeypore Block

SHAKTI MOHAPATRA
BDO
Jeypore Block